MA'ADEN معادن

Saudi Arabian Mining Company شركة التعدين العربية السعودية

Project **Mansourah Massarah Gold Project**

Customer: **MA'ADEN GOLD AND BASE METALS (MA'ADEN)**

Title: **DESIGN CALCULATION**
3640 LOW GRADE CONDITIONING, LEACHING AND ADSORPTION
DESIGN OF CRANE RAIL FOUNDATION

Document Number: **MD-216-3640-EG-CV-CAL-1328**

Revision: **D01**

Revision Date: **23.11.2023**

Status: **AS BUILT**

Outotec Document Number:	900707	GAU01	HL13	CED01	36404	OU100695973	3
L&T Document Number:	O19045	450	C	K	24387	001	3

REVISION HISTORY

Rev	Date	Revision Text	Prepared By	Reviewed By	Approved By	Employer
A01	10.09.2020	FIRST ISSUE	AvG	SJM	AG	
A02	16.11.2020	REVISED AS PER COMMENTS DATED 08/10/2020	AvG	SJM	AG	
C01	15.12.2020	ISSUED FOR CONSTRUCTION	AvG	SJM	AG	
D01	23.11.2023	AS BUILT	AvG	SJM	AG	

TABLE OF CONTENTS

DEFINITIONS AND ABBREVIATIONS 3

1. INTENT 4

2. EXECUTIVE SUMMARY 4

3. SCOPE 4

4. DESIGN REQUIREMENTS 5

    4.1 Design Loads 5

5. CONCRETE FOUNDATIONS 5

    5.1 Design 5

    5.2 Materials 5

    5.3 Foundations for Aboveground Tanks 5

    5.4 Minimum Concrete Cover 5

    5.5 Allowable Soil Bearing Capacity 6

6. DESIGN CALCULATION FOR FOUNDATION 6

Reference 11

ATTACHMENT 1 LOAD DATA DRAWINGS 11

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

DEFINITIONS AND ABBREVIATIONS

Document	:	Information and the medium on which it is contained (ISO 9000:2015)
EMPLOYER	:	'EMPLOYER' means MA'ADEN GOLD AND BASE METALS (MGBM) and the PMC American Bechtel Inc. or their representatives
Contractor	:	Contractor' means consortium composed of LARSEN & TOUBRO LIMITED, Saudi Arabia AND OUTOTEC SAUDI ARABIA LLC, Saudi Arabia (for IK Contract) and LARSEN & TOUBRO LIMITED – ECC Construction Group – (SHJ BR) and OUTOTEC ENGINEERING DMCC, Dubai (for OOK Contract).
'PMT'	:	Ma'aden Project Management Team
'MMGP Project'	:	Mansourah Massarah Gold Processing Project
Attribute	:	Information element that describes a document or tag.
Supplier	:	An entity (supplier, consultant, sub-contractor) under the direct project management of Contractor
Sub-Supplier	:	A sub entity (supplier, consultant, sub-contractor) under the direct project management of Contractor.
QA	:	Quality Assurance
QC	:	Quality Control
Works	:	Full scope of the EPC Contract including the engineering, procurement, construction, commissioning and associated activities

PROPRIETARY & CONFIDENTIAL
The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

1. INTENT

This document is to Prepare for design of **Crane Rail Foundation (3640)**. The analysis & design is carried out in accordance with project specifications and codes & standards. The design calculation ensures the safety and serviceability of the foundation system.

2. EXECUTIVE SUMMARY

The Saudi Arabian Mining Company (Ma'aden) has announced that its wholly-owned subsidiary, Ma'aden Gold and Base Metals Company, have issued a Notice of Award to Outotec and Larsen & Toubro Consortium to complete the engineering, procurement, construction, pre-commissioning, commissioning and start-up assistance of the Mansourah & Massarah (MMGP) Gold Project.

MMGP project will become Ma'aden's largest ever gold project, producing an average of 250,000 ounces of gold per year over the life of mine. Mansourah-Massarah is situated within the Central Arabian Gold Region (CAGR), approximately 320km northeast of Taif towards Riyadh and about 35 km southeast of Hufairah, which is a small village situated on Jeddah - Riyadh highway. Mansourah - Massarah gold deposits are located 22°38'6.40"N; 42°44'22.90"E, and 22°42'1.40"N; 42°41'58.40"E respectively, approximately 537 km east of Jeddah and 77 km southeast of the town of Zalim.

The plant throughput capacity is 4000000t/a and is required to operate on a continuous basis at nominally 24 hours per day and 7 days a week.

3. SCOPE

The analysis has been carried out in Excel. For member strength calculation force values are directly taken from Load Data Provided.

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

4. DESIGN REQUIREMENTS

4.1 Design Load

All Design Loads are indicated in Gantry Crane Drawing (Doc. No. MD-216-3660-EG-ME-GAD-V557-1003) attached in Attachment 1. Also indicated in Civil, Structural and Architectural Design Criteria (Doc. No. MD-216-1000-EG-ST-CRT-1001) Clause 4.2.

5 CONCRETE FOUNDATIONS

5.1 Design

Design of foundations shall be in accordance with SBC-304, ACI 318M and API 650.

5.2 Materials

Concrete Strength of 28 days

- Foundation and Structural Members: 35 MPa
- Blinding Concrete below foundation bases: 15 MPa

Reinforcement Grade

- Deformed Bar: ASTM A 615 / A 615M Grade 60 (fy = 420MPa)

5.3 Foundations for Aboveground Tanks

Foundation shall be Earth Foundation with a Concrete Ring wall. The design calculations are prepared as per recommendation of standard API 650 - Annex B.

5.4 Minimum Concrete Cover

Concrete Exposure	Member	Minimum Cover(mm)
Exposed to weather or contact with ground	Wall	50
	Foundation	50

PROPRIETARY & CONFIDENTIAL
The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

5.5 Allowable Soil Bearing Capacity

The net safe bearing capacity of soil for foundations design has been considered as 450 kN/m^2 at 1.5m depth below EGL (ie. RL 910.70m) refer Table 5 - BH-27 of Geotechnical Report (MD-216-3000-EG-CV-RPT-1008).


6. DESIGN CALCULATION FOR FOUNDATION

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.


DESIGN OF FOUNDATION FOR CRANE

	Along-X	Along-Z
Thickness of wall		0.45m
Size of fdn. raft:	2.40m	3.15m
Thickness of raft:	0.45 m	
Original Gr. Level:	0.00 m	
Finished Gr. Level:	0.00 m	
U/S of B/Pl Above GL:	1.35 m	
U/S level of fdn:	-1.50 m	
Unit weight of conc:	25 kN/m^3	
Unit weight of soil:	18 kN/m^3	



Calculation of Weight of Foundation :


Weight of raft = (2.4*3.15*0.45*25) =	85.05KN
Weight of Wall = (2.4*3.15*0.45*25) =	85.05KN
Weight of soil = ((2.4*3.15)-(3.15*0.45))*1.05*18 =	116.09KN
Total =	286.19KN



Design Input:

Characteristic strength of concrete, f '$_c$=	35 MPa
Yield stress of steel reinforcement, f_y=	420 MPa
Clear cover for main reinforcement bars =	50mm
Dia. of bars provd. along X direction at bottom =	16mm
Dia. of bars provd. along X direction at top =	12mm
Dia. of bars provided along Z direction at bottom=	12mm
Dia. of bars provided along Z direction at top=	12mm
Mininum percentage of reinforcement at bottom=	0.18%
Mininum percentage of reinforcement at top=	0.09%
Dia. of bars provided wall vertical =	16mm

Effective depth of slab along X direction = 386mm = 0.386m
Effective depth of slab along Z direction = 394mm = 0.394m
Effective depth of Wall = 392mm = 0.392m
Clear projection along X direction = 0.975m



H_X=Force along X-X direction

Hz=Force along Z-Z direction

M_X=Moment about X-X direction


Mz=Moment about Z-Z direction

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

Basic Load Cases :

Wheel loads (vertical)	Force component from the mass of the crane and the hoist(s) per crane axis	Qc,min,1	97.9	Qc,max,1	103.5	[kN]
		Qc,min,2	105.9	Qc,max,2	111.5	[kN]
	Force component from mass of hoist load per crane axis	Qh,min,1	10.0	Qh,max,1	55.2	[kN]
		Qh,min,2	9.8	Qh,max,2	55.2	[kN]
Lateral loads (horizontal)	Force from the acceleration of the crane with hoist load (mass force)	HT,min	10.8	HT,max	16.7	[kN]
	skewing force (coefficient of frictional contact <= 0,3)	S			107.6	[kN]
	Horizontal force from skewing per crane axis	HS,min,1	0.0	HS,max,1	0.0	[kN]
		HS,min,2	5.9	HS,max,2	101.7	[kN]
Longitudinal loads (horizontal) (per runway beam)	Force from the acceleration of the crane with hoist load (mass force)	HL			24.5	[kN]
	Force from impact on buffer (collision force) (motion limiter taken into account)	HB1			59.5	[kN]



PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

Loads on Rail :-

Maximum Vertical Load (Q_C max 2 + Q_H max 2)= 111.5 + 55.2 kN
= 166.7 kN

Maximum Horizontal Load(H_S max 2 + H_T max 2)= 101.7 + 16.7 kN
118.4 kN

Sl. No	Basic Load Case	V (kN)	Hx (kN)
1	Dead Load (D)	0.0	0.0
2	Crane Load (Cr)	166.7	118.4

Combined Load Cases:		**Load at top of foundation**					**Load at bottom of foundation**				
Load Case	Load Combination	V (kN)	Hx (kN)	Mz (kN-m)	Hz (kN)	Mx (kN-m)	V (kN)	Hx (kN)	Mz (kN-m)	Hz (kN)	Mx (kN-m)
Allowable Stress Design											
201	D + Cr	166.7	118.4	0.0	0.0	0.0	452.89	118.40	337.44	0.00	0.00
Ultimate Conditions											
301	1.2 D + 1.6 Cr	266.7	189.4	0.0	0.0	0.0	610.15	189.44	539.90	0.00	0.00

Check for overturning and sliding:

Load Cases:		Load at b/o fdn					F.O.S. Mz	F.O.S. Mx	F.O.S. Hx	F.O.S. Hz
		V (kN)	Hx (kN)	Mz (kNm)	Hz (kN)	Mx (kNm)				
201	D + Cr	452.89	118.40	337.44	0.00	0.00	1.61		1.53	

PROPRIETARY & CONFIDENTIAL
The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

DESIGN OF FOUNDATION FOR CRANE 0

Load Combination & Calculation of Base pressure


Max. Base pressure = $p_{max} = (V/(Lx.Lz)) + (6.My/((Lx)^2.Lz) + (6.Mx/(Lx.(Lz)^2)$

Min. Base pressure = $p_{min} = (V/(Lx.Lz)) - (6.My/((Lx)^2.Lz) - (6.Mx/(Lx.(Lz)^2)$

Surcharge load = 20 kN/m²

Net safe bearing capacity of soil for DL, LL= 375 kN/m² For Wind load/Seis. load cas 468.75 kN/m²

Gross safe bearing capacity of soil for DL, LL= 402 kN/m² For Wind load/Seis. load cas 495.75 kN/m²



Load Case	Load Combination	Design Load/moments			Base Pressure (kN/m²)													
		V (kN)	Mz (kN-m)	Mx (kN-m)	V/ (Lx.Lz)	6.Mz/ $(Lx)^2.Lz$	6.Mx/ $Lx.(Lz)^2$	p_1 (p_{max})	p_2	p_4	p_3 (p_{min})	(p_{max}-γh)	$p_{avx(max)}$	$p_{avx(min)}$	$p_{avz(max)}$	$p_{avz(min)}$	Remarks
201	D + Cr	452.89	337.44	0.00	59.91	111.59	0.00	223.17	223.17	0.00	0.00	196.17	223.17	0.00	111.59	111.59	**O.K**
301	1.2 D + 1.6 Cr	610.15	539.90	0.00	80.71	178.54	0.00	342.65	342.65	0.00	0.00	315.65	342.65	0.00	171.33	171.33	

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

DESIGN OF FOUNDATION FOR CRANE

Calculation of Bending Moment and Shear Force in X direction :

p_{1x} =pressure at the face of column at section 1x-1x in kN/m^2.

p_{2x} =pressure at the face of column at section 2x-2x in kN/m^2.

p_{3x} =pressure at a distance 'd' from the face of column at section 3x-3x in kN/m^2.

BM_{1x} =Moment at the face of column at section 1x-1x in kN-m/m.

BM_{2x} =Moment at the face of column 2x-2x in kN-m/m.

SF_{3x} = Oneway shear force at a distance 'd' from the face of column at section 3x-3x in kN/m.

SF (punching) = Punching Shear Force at a distance 0.5d from the face of column in kN/m.

Punching perimeter= ((3.15+2*0.5*0.394)+(0.45+2*0.5*0.394))*2

= 8.776 m


Punching Area= ((3.15+2*0.5*0.394)*(0.45+2*0.5*0.394))

= 2.99 m^2 Punching shear stress to be checked

Downward pressure due to self weight of raft and soil = (0.45*25+1.05*0.45*18)

= 30.15 kN/m^2

Area of footing, A_f= 7.56 m^2



Load Case	Load Combination	p_{1x}	p_{2x}	p_{3x}	$B.M_{1x}$	$B.M_{2x}$	$S.F_{3x}$	$S.F_{(punching)}$
301	1.2 D + 1.6 Cr	203.45	139.20	258.56	126.48	7.72	159.30	539.71

Overhang = 0.975 m

Effective depth = 0.386 m

Location	Mux (kN-m)	ϕ Kn = M_{u1}/bd^2 (N/mm^2)	Kn (N/mm^2)	ρ=	Ast (mm^2)	Minm. Ast (mm^2)	Bar Dia	Spacing reqd.(mm)	Maxm spacing (mm)	Spacing provd. (mm)	Ast (mm^2)
At bottom	126.48	0.85	1.13	0.003	1060.80	694.80	16ϕT	189.54	300	175	1148.93
At top	15.00	0.10	0.13	0.000	0.00	347.40	12ϕT	325.55	300	200	565.49

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

DESIGN OF FOUNDATION FOR CRANE

Check against one-way shear force at a distance d from face of column:

Allowable shear stress, (ϕ Vc)/bd = 0.740 N/mm^2

Shear at a distance 'd' from face of column, Vu= 159.30 kN/m

Shear stress , τ_v= (159.3*1000)/(1000*386)

= 0.41 N/mm^2 **OK**

Check against Two-way shear force at a distance d/2 from face of column:

Design punching shear at a distance d/2 from face of column, Vu= 539.71 kN

Strength of Concrete in shear Vc1 = 4294.49 kN **Table 22.6.5.2_ (a)**

Strength of Concrete in shear Vc2 = 4809.28 kN **Table 22.6.5.2_ (b)**

Strength of Concrete in shear Vc3 = 6680.31 kN **Table 22.6.5.2_ (c)**

Design Vc= 4294.49 kN

Allowable shear stress, (ϕ Vc)/bd = 0.95 N/mm^2

Design punching shear stress, τ = (539.71*1000)/(8776*394)

= 0.16 N/mm^2 **No shear reinforcement reqd.**

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.

This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

DESIGN OF FOUNDATION FOR CRANE

Calculation of distribution reinf in Z direction :

Effective depth = 0.394 m

Location	Mux (kN-m)	ϕ Kn = M_{u1}/bd^2 (N/mm^2)	Kn (N/mm^2)	ρ=	Ast (mm^2)	Minm. Ast (mm^2)	Bar Dia	Spacing reqd.(mm)	Maxm spacing (mm)	Spacing provd. (mm)	Ast (mm^2)
At bottom	50.00	0.32	0.43	0.001	405.82	354.60	12ϕT	278.69	300	200	565.49
At top	20.00	0.13	0.17	0.000	161.62	354.60	12ϕT	318.94	300	200	565.49

Check against one-way shear force at a distance d from face of column:

Allowable shear stress, (ϕ Vc)/bd = 0.740 N/mm^2

Shear at a distance 'd' from face of column, Vu= 275.83 kN/m

Shear stress , τ_v= (275.83*1000)/(1000*394)

= 0.70 N/mm^2 **OK**

Calculation of reinf in Wall :

Effective depth = 0.392 m

Load Case	Load Combination	$B.M_{wall}$ (kN-m)	$S.F_{wall}$ kN/m
301	1.2 D + 1.6 Cr	144.34	60.14

Location	Mux (kN-m)	ϕ Kn = M_{u1}/bd^2 (N/mm^2)	Kn (N/mm^2)	ρ=	Ast (mm^2)	Minm. Ast (mm^2)	Bar Dia	Spacing reqd.(mm)	Maxm spacing (mm)	Spacing provd. (mm)	Ast (mm^2)
At Vertical	144.34	0.94	1.25	0.003	0.00	965.00	16ϕT	208.35	300	200	1005.31
At Horizontal	50.00	0.33	0.43	0.001	0.00	463.20	12ϕT	244.17	300	200	565.49

Check against one-way shear force at a distance d from face of column:

Allowable shear stress, (ϕ Vc)/bd = 0.740 N/mm^2

Shear at a distance 'd' from face of column, Vu= 60.14 kN/m

Shear stress , τ_v= (60.14*1000)/(1000*386)

= 0.16 N/mm^2 **OK**

SUMMARY OF REINFORCEMENT IN RAFT:

Along X Direction :

At Bottom **16ϕT** **175** c/c

At Top **12ϕT** **200** c/c

Along Z Direction :

At Bottom **12ϕT** **200** c/c

At Top **12ϕT** **200** c/c

SUMMARY OF REINFORCEMENT IN WALL:

Vertical Direction:

16ϕT **200** c/c

Horizontal Direction :

12ϕT **200** c/c

PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

REFERENCE


Reference is made to codes, standards and specifications as indicated in Civil, Structural and Architectural Design Criteria (Doc. No. MD-216-1000-EG-ST-CRT-1001) Clause 4.1.

ATTACHMENT 1 LOAD DATA DRAWING


PROPRIETARY & CONFIDENTIAL

The contents of this document are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without the prior written permission of Outotec is prohibited.
This document is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.


DRAWING NUMBER MD-216-3660-EG-ME-GAD-V557-1003 REV A01




CROSS TRAVEL WHEEL DETAILS




RADIO REMOTE




ABUS PENDANT




LONG TRAVEL RAIL DETAILS




load hook: E 4.0 - V
SWIVEL TYPE SINGLE SHANK WITH SAFETY LATCH AS PER DIN15401



CROSS TRAVEL RAIL DETAILS




LOAD HOOK: AS PER DIN 15401



4/2 FALLS ROPE REEVING ARRANGEMENT

HOOK BLOCK TABLE

EQUIPMENT NUMBER	DIMENSION "A" (MM)	DIMENSION "B" (MM)	DIMENSION "C" (MM)	DIMENSION "D" (MM)	DIMENSION "E" (MM)	DIMENSION "F" (MM)	DIMENSION "G" (MM)	DIMENSION "H" (MM)	DIMENSION "I" (MM)	DIMENSION "K" (MM)	DIMENSION "M" (MM)	WIRE ROPE DIA ød(MM)
3640-CRN-003 (20T HOIST)	384	368	278	310	310	165	112	95	90	69	100	16




FESTOON DETAILS

3640-CRN-001


LOW GRADE CARBON IN LEACHIN AREA CRANE

Load effects and relevant force components:


Wheel loads (vertical)	Force component from the mass of the crane and the hoist(s) per crane axis	Qc,min,1	97.9	Qc,max,1	103.5	[kN]
		Qc,min,2	105.9	Qc,max,2	111.5	[kN]
	Force component from mass of hoist load per crane axis	Qh,min,1	10.0	Qh,max,1	55.2	[kN]
		Qh,min,2	9.8	Qh,max,2	55.2	[kN]
Lateral loads (horizontal)	Force from the acceleration of the crane with hoist load (mass force)	HT,min	10.8	HT,max	16.7	[kN]
	skewing force (coefficient of frictional contact <= 0,3)	S			107.6	[kN]
	Horizontal force from skewing per crane axis	HS,min,1	0.0	HS,max,1	0.0	[kN]
		HS,min,2	5.9	HS,max,2	101.7	[kN]
Longitudinal loads (horizontal) (per runway beam)	Force from the acceleration of the crane with hoist load (mass force)	HL			24.5	[kN]
	Force from impact on buffer (collision force) (motion limiter taken into account)	HB1			59.5	[kN]




LONG TRAVEL WHEEL LOADS FOR
CRANE CAPACITY - 20 T, CRANE SPAN - 40000 MILLIMETER
TYPE OF CRANE - DOUBLE GIRDER GANTRY CRANE
TOTAL NUMBER OF LONG TRAVEL WHEELS - 08 NUMBERS(MAX WHEEL LOAD = 166.7 kN)
SAIZE OF LONG TRAVEL RAILS - A75 AS PER DIN 536



CT WHEEL DETAILS



LT WHEEL DETAILS



KEY PLAN OF CRANE

DOCUMENT NUMBER	REFERENCE DOCUMENTS	REV	DATE	REVISION DESCRIPTION	DRN	CHK	ENG	APP	EMP
MD-216-3650-EG-ME-GAD-1035	LOW GRADE CONDITIONING/LEACHING/ABSORPTION AREA SECTION C-C								
MD-216-3650-EG-ME-GAD-1032	LOW GRADE CONDITIONING/LEACHING/ABSORPTION AREA PLAN VIEW								
MD-216-3650-EG-ME-DAT-V557-1001	DATA SHEET LOW GRADE CONDITIONING -LEACHING - ABSORPTION GANTRY CRANE	A03	05/07/2020	ISSUED FOR APPROVAL					
MD-216-3650-EG-ME-GAD-V557-1004	GENERAL ARRANGEMENT LOW GRADE CIL GANTRY CRANE MAJOR COMPONENTS & ACCESSORIES	A02		ISSUED FOR APPROVAL					
MD-216-3650-EG-ME-GAD-V557-1002	GENERAL ARRANGEMENT LOW GRADE CIL GANTRY CRANE PLAN & ELEVATION VIEW	**A01**	**02/04/2020**	**ISSUED FOR APPROVAL**	--	RKM	--	NBR	

Ace Crane Systems LLC
P.O. Box 231314
Dubai United Arab Emirates
T +971(6) 5269080; F +971(6) 5269096
E info@acecranes.com; W www.acecranes.com

DRAWING NUMBER						REVISION
LT102156_SK_GA_CR03.2						2
DATE	03/07/2020	DATE	05/07/2020	DATE	05/07/2020	
DRAWN	SAN	CHECKED	KGN.	APPROVED	GRU	

LARSEN & TOUBRO DRAWING NUMBER		REVISION
019045_255_J_V_17642_001		2
OUTOTEC DRAWING NUMBER	DOCUMENT ID	REVISION
900707__GAU01__EE13__MTL01__36613	OU100682139	2

LARSEN & TOUBRO

This drawing is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

Outotec

The content of these documents are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without prior written permission of Outotec is prohibited.

MA'ADEN معادن
Saudi Arabian Mining Company شركة معادن العربية السعودية

This document and the information contained herein is Ma'aden proprietary know-how. This document or any part thereof should not be reproduced, stored in a retrieval system or transmitted by any means, electronic or otherwise, or divulged without prior written permission of Ma'aden.

DRAWN	--	--
CHECKED	RKM	02/04/2020
ENGINEER	--	--
APPROVED	NBR	02/04/2020
EMPLOYER		
SCALE	1:125	A1

MANSOURAH - MASSARAH GOLD PROJECT
GENERAL ARRANGEMENT
LOW GRADE CONDITIONING-LEACHING-ADSORPTION
CRANE MAJOR COMPONENTS AND ACCESSORIES

DRAWING NUMBER MD-216-3660-EG-ME-GAD-V557-1003 REV A03